



# PANVEL MUNICIPAL CORPORATION

Tal- Panvel, Dist – Raigad, Panvel – 410 206.

E mail – [panvelcorporation@gmail.com](mailto:panvelcorporation@gmail.com)

Tel – (022) 27458040/41/42

NO.2019/PMC/TP/BP/ 558 /2019

Date : 21 / 02 / 2019

To,  
M/s. Suasth Healthcare (India) Pvt. Ltd.,  
Plot No – 01, Sector – 20, Opp. PHQ,  
Kalamboli, Navi Mumbai.

**SUB:- 2<sup>nd</sup> Amended Development Permission for Super Specialty Hospital Building on Plot No – 01, Sector – 20, At - Kalamboli, Navi Mumbai.**

- REF:-
- 1) Your Architect's application No. 15123, dt- 07/09/2018.
  - 2) Commencement Certificate No. CIDCO/ATPO(BP)/2011/042, Dated – 07/04/2011.
  - 3) 1<sup>st</sup> Amended Commencement Certificate No. CIDCO/BP/12051/ATPO (NM&K)/1762, Dated – 13/11/2013.
  - 4) Fire NOC No. PMC/FIRE/10850/2018, Dated – 27/12/2018.
  - 5) Aesthetic Approval No. CIDCO/(PLNG)/SP-2018/148, Dated – 25/05/2018.
  - 6) Additional FSI NOC No. CIDCO/M(TS-III)/2018/4009, Dated – 30/11/2018.

Sir,

Please refer to your application for 2<sup>nd</sup> Amended development permission for Super Specialty Hospital Building on Plot No – 01, Sector – 20, At - Kalamboli, Navi Mumbai.

The 2<sup>nd</sup> Amended development permission is hereby granted to construct Super Specialty Hospital Building on the plot mentioned above.

The Developers / Builders/ Owners shall take all precautionary measures for prevention of Malaria breeding during the construction period of the project. If required , you can approach Health Department PMC, for orientation program and pest control at project site to avoid epidemic.

You have to pay the necessary charges due to GST if applicable in future as per Panvel Municipal Corporation policy and as informed to you in writing and if not paid the permission granted will be revoked.

You will ensure that the building materials will not be stacked on the road during the construction period.

Thanking you,

Approved By Hon. Commissioner  
Panvel Municipal Corporation

Assistant Director of Town Planning  
Panvel Municipal Corporation

C.C.TO:- 1) Architect,  
Liladhar Parab,  
107, Thacker Tower, Plot No – 86,  
Sector – 17, Vashi, Navi Mumbai.





# PANVEL MUNICIPAL CORPORATION

Tal- Panvel, Dist – Raigad, Panvel – 410 206.

E mail – [panvelcorporation@gmail.com](mailto:panvelcorporation@gmail.com)

Tel – (022) 27458040/41/42

NO.2019/PMC/TP/BP/ 558 /2019

Date : 21 / 02 / 2019

## 2<sup>nd</sup> AMENDED COMMENCEMENT CERTIFICATE

Permission is hereby granted under section – 45 of the Maharashtra Regional and Town Planning Act.1966 (Maharashtra XXXIV) of 1966 to, M/S. SUASTH HEALTHCARE (INDIA) PVT. LTD., for Plot No-01, Sector – 20, Kalamboli, Navi Mumbai. As per the approved plans and subject to the following conditions for the 2<sup>nd</sup> Amended development work of the Proposed Super Specialty Hospital Building on (Basement I & II, Lower ground & Upper Ground + 2 Floors) Total Built Up Area = 23892.451 sq.mt.,

(Unit – Super Specialty Hospital Building)

1. This Certificate is liable to be revoked by the Corporation if:-
  - 1(a) The development work in respect of which permission is granted under this certificate is not carried out or the use thereof is not in accordance with the Sanctioned plans.
  - 1(b) Any of the conditions subject to which the same is granted or any of the restrictions imposed upon by the corporation is contravened.
  - 1(c) The commissioner is satisfied that the same is obtained by the applicant through fraud or Misrepresentation and the applicant and/or any person deriving title under him, in such an event shall be deemed to have carried out the development work in contravention of section – 43 or 45 of the Maharashtra Regional and Town Planning Act- 1966.
2. The applicant shall:-
  - 2(a) Give written notice to the Corporation regarding completion of the work.
  - 2(b) Obtain Occupancy Certificate from the Corporation.
  - 2(c) Permit authorized officers of the Corporation to enter the building or premises for which the permission has been granted, at any time for the purpose of ensuring the building control Regulations and conditions of this certificate.
3. The structural design, building materials, installations, electrical installations etc. shall be in accordance with the provision (except for provision in respect of floor area ratio) as prescribed in the National Building Code or and DCR for A.B.C. class Municipal Council 2013 in force.
4. The Commencement Certificate shall remain valid for period of 1 year from the date of its issue; thereafter revalidation of the same shall be done in accordance with provision of Section – 48 of MRTP Act- 1966 and as per regulations no. 16.1(2) of the DCR for A.B.C. class Municipal Council 2013 in force.
5. The conditions of this certificate shall be binding not only on the applicant but also on its successors and/or every person deriving title through or under him.
6. Prior Permission is necessary for any deviation / Change in Plan.
7. It is Mandatory to provide Temporary Toilet to labours at site during construction period.
8. It is mandatory for the institution to take safety measures while the construction is under progress with respect to the educational activities going on in the respective site.



## PANVEL MUNICIPAL CORPORATION

Tal- Panvel, Dist – Raigad, Panvel – 410 206.

E mail – [panvelcorporation@gmail.com](mailto:panvelcorporation@gmail.com)

Tel – (022) 27458040/41/42

### SCHEDULE RAIN WATER HARVESTING

Rain Water Harvesting in a building site include storage or recharging into ground of rain water falling on the terrace or on any paved or unpaved surface within the building site.

1. The following systems may be adopted for harvesting the rain water drawn from terrace and the paved surface.
  - i) Open well of minimum of 1.00 mt, dia and 6.mt. depth into which rain water may be channeled and allowed after filtration for removing silt and floating material. The well shall be provided with ventilating covers. The water from the open well may be used for non-potable domestic purposes such as washing, flushing and for watering the garden etc.
  - ii) Rain water harvesting for recharge of ground water may be done through a bore well around which a pit of one meter width may be excavated upto a depth of at least 3.00 mt. and refilled with stone aggregate and sand, the filtered rain water may be channeled to the refilled pit for recharging the borewell.
  - iii) An impervious surface underground storage tank of required capacity may be construed in the setback or other open space and the rain water may be channeled to the storage tank. The storage tank shall always be provided with ventilating covers and shall have drawn-off taps suitably placed so that the rain water may be drawn off for domestic, washing gardening and such other purposes. The storage tanks shall be provided with an overflow.
  - iv) The surplus rain water after storage may be recharged into ground through percolation pits or trenches or combination of pits and trenches. Depending on the geomorphological and topographical condition, the pits may be of the size of 1.29mt. width x 1.20 mt. depth. The trenches can be or depth. Terrace water shall be channeled to pits or trenches. Such pits or trenches shall be back filled with media comprising the following materials.
    - a) 40 mm stone aggregate as bottom layer upto 50% of the depth.
    - b) 20 mm stone aggregate as lower middle layer upto 50% of the depth.
    - c) Coarse sand as upper middle layer upto 20% of the depth.
    - d) A thin layer of fine sand as top layer.
    - e) Top 10% of the pits/trenches will be empty and a splash is to be provide in this portion in such a way that roof top water falls on the splash pad.
    - f) Brick masonry wall is to be constructed on the exposed surface of pits/trenches and the cement mortar plastered.

The depth of wall below ground shall be such that the wall prevents lose soil entering into pits/trenches. The projection of the wall above ground shall at least be 15 cms.
    - g) Perforated concrete slabs shall be provided on the pits/trenches
  - v) If the open space surrounding the building is not paved, the top layer upto a sufficient depth shall be removed and refilled with course sand to allow percolation of rain water into ground.
2. The terrace shall be connected to the open well / bore well / storage / tank / recharge pit/trench by mean of HDPE/PVC pipes through filter media. A valve system shall be provided to enable the first washings from roof or terrace catchment, as they would contain undesirable dirt. The mouths of all pipes and pipes openings shall be covered with mosquito (insect) proof wire net. For the efficient discharge of rain water, there shall be at least two rain water pipes of 100 mm diameter for a roof area of 100 sq.mt.
3. Rain water harvesting structures shall be sited as not to endanger the stability of building or earthwork. The structures shall be designed such that no dampness is caused in any part of the walls or foundation of the building or those of an adjacent building.
4. The water so collected/recharged shall as far as possible be used for non-drinking and non-cooking purpose. Provided that when the rain water in exceptional circumstances will be utilized for drinking and/or cooking purpose, it shall be ensured that proper filter management and the separate outlet for by passing the first rain- water has been provided.

Provided further that it will be ensured that for such use, proper disinfectants and the water purification arrangements have been made.

