



Water Treatment Specialist

QUOTATION Ref No. CF/Q/0314/24/25

TO
Mr. Naren Patil
Nashik

Date :22/09/2024

Sub:- Swimming Pool Waterproofing & Tiles Fixing at Site Nashik.

Sir

This has Reference to the between discussion with undersigned subject matter we wish to quote for our lowest competitive rate as follows.

No.	Description	Unit	Qty	Rate	Total Amount
B	SPECIFICATION OF WATERPROOFING /PLASTER				
1	Cleaning :- Cleaning the base of Swimming Pool by brush and broom clearing all loose Particular laintance Foreign body etc.	Sq.ft	1124	5.00	5,620.00
2	Patch Work :- Patch work :Searching for cracks and filling the same with CWC® SMARTCEM PMC60 – High strength non shrink fibre reinforced ready to use mortar.	RFt	225	45.00	10,125.00
4	Injection Grouting :- Searching for honeycomb surface & weak portion & Between Vertical / Horizontal joint each 1mter of the concrete & fixing ½” dia nozzles & pressure grouting the same with cementitious milk admixed with CWC® SMARTCEM C – Non-shrink polymeric waterproof grouting compound, @ 250 gm / 50 Kg bag of cement. Sealing off the nozzles after injection operation is over with CWC® SMART No.03 - Quick setting admixture, admixed with Cement.	Nos	150	450.00	67,500.00
3	Waterproofing: Applying 1st coat of CWC® SMARATCRETE– A Surfacing System for Protecting Concrete and Masonry, mixed with cement in 1:2 proportion over the entire sunken portion.Applying 2nd coat of CWC® SMARTCRETE after 3 to 4 hours, i.e., after the 1st coat has dried. Cement mortar Double Coat Plaster Laving of average 20 mm thick	Sq.ft	1124	145.00	1,62,980.00
Total Basic Amount of A Part					2,46,225.00

C	SPECIFICATION OF GLASS MOSAIC				
1	Supply :- Supply of Tiles Size 50mm x 50mm	Sq.ft	1200	145.00	1,74,000.00

2	Fixing Of ' Glass Mosaic tiles" Size 20 mm x 20mm x4mm with Saint Gobain Weber ,Adhesive , Epoxy grout , Grouting Cleaning & Completed work will be done line & level Grouting –after 24 Hrs. Of Tiles fixing. Grouting will be done After Arial Washing :- Grouting & Finishing Arial Washing will be done.	Sq.ft	1124	140.00	1,57,360.00
Total Basic Amount of B Part					3,31,360.00
Total Basic Amount of A+B					5,77,585.00

TERMS AND CONDITIONS:-

- * Space for stacking the construction material /labour camp will be allowed by the owners at site of work, Also site office
- * Extra items of work which are not mentioned in our schedule of rates and scope of work, and if it is to be carried out,
- * We assume the tentative completion of the work will be 2 to 2.5 Month including ponding & testing of the pool.(
- * Ponding and testing water will be supplied by the owners free of cost at site of work and ponding and testing will be
- * This is the estimate if any item of work is not mentioned in our estimate will be charged extra before taking the work in
- *

Payment :- 60 % Advance on total value with GST
:- 20% Payment after materilas dispatch
:- 15% After Waterproofing Befor tiling work
:- 5% On full complete job with installationn within 1 week.

Taxes :- GST& will be extra as per Actual.

Gurrantee Period :- We Give Gurrantee for 10 Years.

We trust that you will find our offer more suitable and look forward to receive your valued order.

For Crystal Filters

Authorised