

Handling and Andrew

Note: A valid environmental clearance shall be one that has EC identification number & E-Sign generated from PARIVESH.Please quote identification number in all future correspondence.

This is a computer generated cover page.

STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

No. SIA/MH/INFRA2/429372/2023

Environment & Climate Change Department Room No. 217, 2nd Floor, Mantralaya, Mumbai- 400032.

То

M/s.Supreme Sky High LLP, CTS No. 74A/3A, village Deonar, Govandi Station Road, Chembur, Mumbai.

> Subject : Environmental Clearance for Application of EC for Residential project on plot bearing CTS No. 74A/3A at village Deonar in M/E ward at Govandi Station Road, Deonar, Chembur, Mumbai, Maharashtra by M/s.Supreme Sky High LLP

Reference : Application no. SIA/MH/INFRA2/429372/2023

This has reference to your communication on the above-mentioned subject. The proposal was considered by the SEAC-2 in its 208th meeting under screening category 8 (a) B2 as per EIA Notification, 2006 and recommend to SEIAA. Proposal then considered in 265th (Day-1) meeting of State Level Environment Impact Assessment Authority (SEIAA) held on 24th August, 2023. 2.

Sr. No.	Description		Details	
1	Proposal Number	SIA/MH/INFRA2/429372/2023		
2	Name of Project	Environmental Clearance for proposed Residential Bldgs. at Plot bearing CTS No. 74A/3A at village Deonar in M/E ward at Govandi Station Road, Deonar, Chembur, Mumbai, Maharashtra by Supreme Sky-High LLP .		
3	Project category	8 (a) Category (B2)		
4	Type of Institution	Private		
5	Project Proponent	Name Regd. Office address Contact number	Mr. Sunny Bijlani 301, Everest classic, Linking road, Khar west, Mumbai 400052 9819077403	
		e-mail	sunny@supremeuniversal.in	
6	Consultant	Mahabal Enviro Engineers Pvt. Ltd. NABET ACCREDIATION: QCI/NABET/EIA/ACO/17/00427		
7	Applied for	New Project		
8	Location of the project	Plot bearing CTS No. 74A/3A at village Deonar in M/E ward at Govandi Station Road, Deonar, Chembur, Mumbai, Maharashtra		

Brief Information of the project submitted by you is as below:-

9	Latitude and Longitude		Latitude: 19°03'5.46"N & Longitude: 72°55'12.05"E				
10			19,864.90 m ²				
11	Deductions (sq.m.)		1,486.49 m ²				
12	Net Plot	area (sq.m.)		18,378.41 m	n ²		
13	Ground	coverage (m ²)	&%	8,006.82 m ² (43%)			
14	FSI Area (sq.m.)		63,115.43 m ²				
15	Non-FSI (sq.m.)		58,517.77 n	2 1 1			
16	Proposed built-up area (FSI + Non FSI) (sq.m.)		1,21,633,20 m ²				
17	TBUA (m ²) approved by Planning Authority till date		Application submitted for approval to BMC				
18	Earlier EC details with Total Construction area, if any.		Not Applica	Not Applicable (Fresh Proposal)			
19	Construction completed as per earlier EC (FSI + Non FSI) (sq. m.)			No work started			
	Bldg Name	Confg.	Height (m)	Bldg. Name	Confg.	Height (m)	ReasonforModification/Change
20				Wing A	B + G + 3 P+ 4th to 34th Floors	109.95	
				Wing B	B + G + 3 P+ 4th to 34th Floors	109.95	
2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2				Wing C	B + G + 3 P+ 4th to 17th (part) Floors	58.95	-
	<u>र</u> ू 			Wing D	B + G + 3 P+ 4th to 33rd Floors	109.95	
		ĠĂ, Ę		Wing E	2 B + G + 1st to 21st floors	67.85	
21	No. of Tenements & Shops			Residential Flats: 692 Nos., Commercial Area : 898.29 m ²			
22	Total Population			3,753 Nos.			
23	Total Water Requirements CMD			501 KLD			

EC Identification No. - EC23B038MH145475 File No. - SIA/MH/INFRA2/429372/2023 Date of Issue EC - 27/09/2023

Page 3 of 11

24	Under Ground Tank (UGT) location	Basement				
25	Source of water	BMC				
26	STP Capacity & Technology	520 KLD capacity with MBBR technology				
27	STP Location	Basement				
28	Sewage Generation CMD & % of sewage discharge in sewer line	Sewage generation: 465 KLD; Disposal in Municipal sewer: 35%				
29	Solid Waste Management during Construction Phase	Туре	Quantity (kg/d)	Treatment / disposal		
	and the second second second	Dry waste	10	Handed over to local body		
		Wet waste	15	Handed over to local body		
		Construction waste	3532	Will be handled as per		
		Demolition waste	7612	Construction Waste Rule, 2016		
30	Total Solid Waste Quantities	Dry waste	740	Handed over to local body		
50	with type during Operation	Wet waste	1109	Mechanical Composting Unit		
	Phase & Capacity of OWC to be installed	E-Waste	5.0	Handed over to Authorized recycler		
		STP Sludge (dry)	5.0	STP sludge will be composted		
31	RG Area in Sq. m.	RG required -4594.40 m^2				
		RG provided on Mother earth $-$ 4701.83 m ²				
		RG provided on Podium: 4072.05 m ²				
		Total - 8773.88 m ²				
		Existing trees on plot: 104				
		Number of trees to be planted: a) In RG area: 230 Nos.				
		o) In Miyawaki	Plantation	(with area); 230 m^2 ; 460 Nos.		
		Number of trees to be Cut: 35 Nos.Number of trees to be Transplanted: 16 Nos.				
	Se her s	 Number of trees to be Retained: 53 Nos. Total Trees on plot: 759 Nos. (Including existing + new plantation + Miyawaki) 				
	Power requirement	During Operation Phase:				
32		Details		ANI		

		Demand load	6.8 MW	
33	Energy Efficiency	a) Total Energy saving (%): 15%		
		b) Solar energy (%): 5%		
34	D.G. set capacity	2 x 500 kVA (1000 kVA)		
35	No. of 4-W & 2-W Parking with 25% EV	4-W: 1245 & 2-W: 109 Nos. (EV charging points: 25%)		
36	No. & capacity of Rain water	2 RWH tanks with 1	20 KL total canacity	
	harvesting tanks /Pits	2 RWH tanks with 120 KL total capacity		
37	Project Cost in (Cr.)	Rs. 550.86 Cr		
38	EMP Cost	 a) Construction Phase: Rs.180 Lakhs/Annum. b) Operation Phase: 1.Capital Cost: Rs. 967 Lakh, 2.O&M: Rs. 99 Lakh/yr (Including DMP cost) 		
39	CER Details with justification if anyas per MoEF&CC circular dated 01/05/2018			
40	Details of Court Cases/litigations w.r.t the project and project location, if any.	No Court case is pending against the project		

3. Proposal is a new construction project. Proposal has been considered by SEIAA in its 265th (Day-1) meeting held on 24th August, 2023. and decided to accord Environment Clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implantation of following terms and conditions-

Specific Conditions:

A. SEAC Conditions-

- 1. PP to submit IOD/IOA/Concession Document/Plan Approval or any other form of documents as applicable clarifying its conformity with local planning rules and provisions as per the Circular dated 30.01.2014 issued by the Environment Department, Govt. of Maharashtra.
- PP to obtain following NOCs and remarks:
 a)Water supply;
 b) Sewer connection;
 c) SWD NOC/remarks;
 d) Tree NOC;
 e) SWM/C& D NOC;
 f) Railway NOC.
- 3. PP to submit architect certificate mentioning that RG area proposed is excluding the area of structures (i.e. Club House, DG Sets, STP & OWC) & parking proposed in RG & all required RG area is provided on mother earth as per Apex Court order.
- 4. PP to revise water balance considering tanker water as make-up water for swimming pool; PP to reduce discharge of treated water up to 35%; PP to submit undertaking/NOC from concerned authority/ agency/third party for use of excess treated water generated in the project.
- 5. PP to relocate parking proposed in RG area & above the STP.
- 6. PP to relocate UGTs of Wing E to the 1st basement such that top of the UGTs are flush to the ground level.

- 7. PP to maintain 3 Mtr. distance between STP & OWC.
- 8. PP to relocate flushing tank adjacent to the STP.
- PP to provide air cleaning system in addition to the basement ventilation & include cost of basement ventilation and air cleaning system in the EMP and accordingly submit revised EMP of operation phase.

B. SEIAA Conditions-

- 1. PP has provided mandatory RG area of 4701.83 m2 on mother earth without any construction. Local planning authority to ensure the compliance of the same.
- 2. Local planning authority i.e. MCGM to ensure that, PP obtains the railway NOC before the grant of Commencement certificate (CC).
- 3. PP to keep open space unpaved so as to ensure permeability of water. However, whenever paving is deemed necessary, PP to provide grass pavers of suitable types & strength to increase the water permeable area as well as to allow effective fire tender movement.
- 4. PP to achieve at least 5% of total energy requirement from solar/other renewable sources.
- 5. PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA III dt.04.01.2019.
- SEIAA after deliberation decided to grant EC for-FSI- 61,982.93 m2, Non FSI-58,019.10 m2, total BUA- 1,20,002.03 m2. (Plan approval No- P-15479/2023/(CTS NO.74A/3A)/M/E WARD/DEONAR-E/337/1/NEW, dated-) (Restricted as per approval)

General Conditions:

a) Construction Phase :-

- I. The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. Disposal of muck, Construction spoils, including bituminous material during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in the approved sites with the approval of competent authority.
- III. Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- IV. Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
- V. Arrangement shall be made that waste water and storm water do not get mixed.
- VI. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices.
- VII. The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
- VIII. Permission to draw ground water for construction of basement if any shall be obtained

from the competent Authority prior to construction/operation of the project.

- IX. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
- X. The Energy Conservation Building code shall be strictly adhered to.
- XI. All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
- XII. Additional soil for levelling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
- XIII. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- XIV. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
- XV. The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
- XVI. Vehicles hired for transportation of Raw material shall strictly comply the emission norms prescribed by Ministry of Road Transport & Highways Department. The vehicle shall be adequately covered to avoid spillage/leakages.
- XVII. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
- XVIII. Diesel power generating sets proposed as source of backup power for elevators and common area illumination during construction phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel is preferred. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
 - XIX. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings by a separate environment cell /designated person.
- B) Operation phase:-
 - I. a) The solid waste generated should be properly collected and segregated. b) Wet waste should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. c) Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
 - II. E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
 - III. a) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Treated

effluent emanating from STP shall be recycled/ reused to the maximum extent possible. Treatment of 100% grey water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP. b) PP to give100 % treatment to sewage /Liquid waste and explore the possibility to recycle at least 50 % of water, Local authority should ensure this.

- IV. Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement.
- V. The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
- VI. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- VII. PP to provide adequate electric charging points for electric vehicles (EVs).
- VIII. Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
- IX. A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
- X. Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes.
- XI. The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at parivesh.nic.in
- XII. A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
- XIII. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM. SO2, NOx (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.
- C) General EC Conditions:-

- I. PP has to strictly abide by the conditions stipulated by SEAC& SEIAA.
- II. If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
- III. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
- IV. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
- V. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
- VI. No further Expansion or modifications, other than mentioned in the EIA Notification, 2006 and its amendments, shall be carried out without prior approval of the SEIAA. In case of deviations or alterations in the project proposal from those submitted to SEIAA for clearance, a fresh reference shall be made to the SEIAA as applicable to assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.
- VII. This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.

4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.

5. This Environment Clearance is issued purely from an environment point of view without prejudice to any court cases and all other applicable permissions/ NOCs shall be obtained before starting proposed work at site.

6. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.

7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, amended from time to time.

8. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the

Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.

9. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1st Floor, D-Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

Pravin Darade (Member Secretary, SEIAA)

Copy to:

- 1. Chairman, SEIAA, Mumbai.
- 2. Secretary, MoEF & CC, IA- Division MOEF & CC
- 3. Member Secretary, Maharashtra Pollution Control Board, Mumbai.
- 4. Regional Office MoEF & CC, Nagpur

1 1.5 5.000

- 5. District Collector, Mumbai Suburban.
- 6. Commissioner, Municipal Corporation of Greater Mumbai.
- 7. Regional Officer, Maharashtra Pollution Control Board, Mumbai.

EC Identification No. - EC23B038MH145475 File No. - SIA/MH/INFRA2/429372/2023 Date of Issue EC - 27/09/2023 Page 11 of 11

. . . .