



Vastukala Consultants (I) Pvt. Ltd.

Page 1 of 4

Vastu/Mumbai/11/2024/012412/2309088 16/7-173-JABS Date: 16.11.2024

Structural Stability Report

Structural Observation Report of Residential Bungalow on 1st & 2nd Floor, Plot No. 11, "Rushikesh Property", Shree Gokul Co-op. Hsg. Soc. Ltd., Survey No. 127/A, Final Plot No. 560, Navi Peth, TPS Scheme No. 3, Near Mhatre Bridge, Village - Parvati Taluka - Haveli, District - Pune, PIN - 411 030, State - Maharashtra, Country -

Name of Owner: Shri. Prashant Suresh Pardeshi

Name of Proposed Purchaser / Client: Darewar Tulana Pandurang & Vivek Shantaram Arote

This is to certify that on visual inspection, it appears that the structure at "Rushikesh Property" at Shree Gokul Co-op. Hsg. Soc. Ltd. is in normal condition and the future life can be reasonably taken under good condition and with proper periodic repairs & maintenance is about 32 years.

General Information:

A.	The state of the s	Introduction
1	Name of Building	"Rushikesh Property" at Shree Gokul Co-op. Hsg. Soc.
		Ltd.
2	Property Address	Residential Bungalow on 1st & 2nd Floor, Plot No. 11,
	100	"Rushikesh Property", Shree Gokul Co-op. Hsg. Soc.
		Ltd., Survey No. 127/A, Final Plot No. 560, Navi Peth, TPS
	The state of the s	Scheme No. 3, Near Mhatre Bridge, Village - Parvati Taluka
		- Haveli, District - Pune, PIN - 411 030, State - Maharashtra,
		Country - India.
3	Type of Building	Residential Bungalow
4	No. of Floors	Ground + 2 Upper Floors
5	Whether stilt / podium / open parking	Open / Covered Parking Space
	provided	
6	Type of Construction	R.C.C. Framed Structure
7	Type of Foundation	R.C.C. Footing
8	Thickness of the External Walls	9" thick brick walls both sides plastered
9	Type of Compound	Brick Masonry Walls
10	Year of Construction	Ground Floor - 1986 (As per Occupancy Certificate)
		1st & 2nd Floor - 2016 (As per Occupancy Certificate)
11	Present age of building	38 years
12	Residual age of the building	32 years Subject to proper, preventive periodic
		maintenance & structural repairs.
13	No. of flats (Per Floor)	Entire Ground + 2 upper floor bungalows
14	Methodology adopted	As per visual site inspection
		20 MINSOID PTEND



Nanded Mumbai

Aurangabad
Pune

Nashik

Rajkot

Ahmedabad Opelhi NCR **Raipur**

2247495919

mumbai@vastukala.co.in www.vastukala.co.in

B1-001, U/B Floor, BOOMERANG, Chandivali Farm Road,

Powai, Andheri East, Mumbai: 400072, (M.S), India

Structural Stability Report Prepared for SBI / RASMECCC Panyel / Darewar Tulana Pandurang & Others (012412 / 2309088) Page 2 of 4

B.	External O	bservation of the Building
1	Plaster	Normal Condition
2	Chajjas	Normal Condition
3	Plumbing	Normal Condition
4	Cracks on the external walls	Not Found
5	Filling cracks on the external walls	Not Found
6	Cracks on columns & beams	Not Found
7	Vegetation	Not Found
8	Leakages of water in the drainage pipes	Not Found
	or water pipes	
9	Dampness external in the wall due to	Not Found
	leakages	
10	Any other observation about the condition	Structural Stability Report from licensed structural
	of external side of the building	engineers not provided for our verification.
С	Internal Observation of the common areas of the building and captioned premises	
1	Beams (Cracks & Leakages)	Not Found
2	Columns (Cracks & Leakages)	Not Found
3	Ceiling (Cracks & Leakages)	Not Found
4	Leakages inside the property	Not Found
5	Painting inside the property	Normal Condition
6	Maintenance of staircase & cracks	Normal ⁻

D	Con	nmon Observation
1	Structural Audit of the Building Under Bye - Laws No. 77 of the Model Bye Laws (Co- Operative Societies Act / Rules)	As per bye Laws No. 77 of Co-Op. Societies bye Laws under the Act the society shall conduct a Structural Audit of the building of the society as follows
2	Remark	i) At the time of site inspection, external condition of the building is normal, dampness not found, leakages are not found & Cracks are not found. ii) Structural Stability Report from licensed structural engineers not provided for our verification.

Conclusion

The captioned building is having Ground + 2 Upper Floors which are constructed in year Ground Floor - 1986 (As per Occupancy Certificate) 1st & 2nd Floor - 2016 (As per Occupancy Certificate). Estimated future life under present circumstances is about 32 years subject to proper, preventive periodic maintenance & structural repairs.

The inspection dated 04.10.2024 of building. The building is well as the property is maintained in normal condition & will stand future life subject to proper, preventive periodic maintenance & Good structural repairs.

Our Observations about the structure are given above.

The above assessment is based on visual inspection only. Separate structural audit from licensed structural engineers is advised to assess exact balance life of structure.

For VASTUKALA CONSULTANTS (I) PVT. LTD.

Sharadkumar Digitally signed by Sharadkumar B. Chalikwar DN: cn=Sharadkumar B. Chalikwar, B. Chalikwar

o=Vastukala Consultants (I) Pvt. Ltd., ou=CMD, email=cmd@vastukala.org, c=IN Date: 2024.11.16 13:06:51 +05'30'



Director


Sharadkumar B. Chalikwar

VASTUKALA

Structural Engineer Licence No. STATE/R/2022/APL/01785 Govt. Reg. Valuer Chartered Engineer (India) Reg No. (N) CCIT/1-14/52/2008-09

SBI Empanelment No.: SME / TCC / 2021 – 22 / 85 / 13





An ISO 9001: 2015 Certified Company



Actual site photographs
























Since 1989







Actual site photographs













