PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT

STAMP OF APPROVAL 2/3

POONA MUNICIPAL CORPORATION * BUILDING CONTROL DEPARTMENT * APPROVED POONA

APPROVED SUBJECTITO CONDITIONS
APPROVED UNDER COMMENCEMENT CERTIFICATE NO. ...

Building Inspector

Duputy Engineer/P.M.C.

THIRD FLOOR AREA CALCULATION								
AREA OF BLOCK								
A	9.70	X	42.35	X	1	=	410.80	SQ. M.
B	9.35	X	0.36	X	1	=	0.89	SQ. M.
TOTAL						=	411.69	SQ. M.
STD. DEDUCTIONS								
1	5.30	X	1.35	X	1	=	7.16	SQ. M.
2	3.35	X	2.00	X	0.50	=	3.35	SQ. M.
3	1.35	X	4.90	X	1	=	6.62	SQ. M.
4	1.35	X	3.65	X	1	=	4.93	SQ. M.
5	0.30	X	7.30	X	1	=	2.19	SQ. M.
6	1.95	X	8.90	X	1	=	17.36	SQ. M.
7	3.05	X	2.10	X	1	=	6.41	SQ. M.
8	0.75	X	2.60	X	1	=	1.95	SQ. M.
9	5.00	X	1.35	X	1	=	7.75	SQ. M.
10	1.10	X	3.00	X	1	=	3.30	SQ. M.
11	2.30	X	2.55	X	1	=	5.86	SQ. M.
12	1.10	X	3.20	X	1	=	3.52	SQ. M.
13	2.00	X	3.05	X	1	=	6.10	SQ. M.
14	4.40	X	4.90	X	1	=	21.56	SQ. M.
L	1.80	X	1.80	X	1	=	3.24	SQ. M.
TOTAL						=	101.28	SQ. M.
NET B/UP OF 1 FLOOR						=	310.32	SQ. M.

4TH,5TH AND 6TH FLOOR AREA CALCULATION								
AREA OF BLOCK								
A	8.95	X	21.95	X	1	=	196.45	SQ. M.
TOTAL						=	196.45	SQ. M.
STD. DEDUCTIONS								
1	2.70	X	2.20	X	1	=	5.94	SQ. M.
2	1.20	X	3.40	X	1	=	4.08	SQ. M.
3	4.25	X	2.10	X	1	=	8.93	SQ. M.
4	1.20	X	1.35	X	1	=	1.62	SQ. M.
5	4.25	X	1.55	X	1	=	6.59	SQ. M.
6	0.35	X	3.00	X	1	=	1.05	SQ. M.
7	1.55	X	2.55	X	1	=	3.95	SQ. M.
8	0.35	X	3.20	X	1	=	1.12	SQ. M.
L	1.80	X	1.80	X	1	=	3.24	SQ. M.
TOTAL						=	36.52	SQ. M.
NET B/UP OF 1 FLOOR						=	159.94	SQ. M.

SECOND FLOOR AREA CALCULATION								
AREA OF BLOCK								
A	9.70	X	33.75	X	1	=	327.38	SQ. M.
B	3.90	X	0.36	X	1	=	0.94	SQ. M.
TOTAL						=	328.31	SQ. M.
STD. DEDUCTIONS								
1	5.15	X	1.35	X	1	=	6.95	SQ. M.
2	3.35	X	2.00	X	0.50	=	3.35	SQ. M.
3	1.35	X	4.90	X	1	=	6.62	SQ. M.
4	1.35	X	3.65	X	1	=	4.93	SQ. M.
5	0.30	X	7.30	X	1	=	2.19	SQ. M.
6	1.95	X	8.90	X	1	=	17.36	SQ. M.
7	0.75	X	2.60	X	1	=	1.95	SQ. M.
8	5.00	X	1.70	X	1	=	8.50	SQ. M.
9	2.00	X	3.05	X	1	=	6.10	SQ. M.
L	1.80	X	1.80	X	1	=	3.24	SQ. M.
TOTAL						=	61.18	SQ. M.
NET B/UP OF 1FLOOR						=	267.13	SQ. M.

MEZZANINE FLOOR AREA CALCULATION								
AREA OF BLOCK								
A	7.75	X	32.40	X	1	=	251.10	SQ. M.
TOTAL						=	251.10	SQ. M.
STD. DEDUCTIONS								
1	3.60	X	4.90	X	1	=	17.64	SQ. M.
2	2.60	X	3.35	X	1	=	8.71	SQ. M.
3	3.60	X	3.80	X	1	=	13.68	SQ. M.
4	3.75	X	7.00	X	1	=	26.25	SQ. M.
5	1.50	X	2.20	X	1	=	3.30	SQ. M.
6	1.80	X	3.60	X	1	=	6.48	SQ. M.
7	3.45	X	4.15	X	1	=	14.32	SQ. M.
8	2.00	X	3.05	X	1	=	6.10	SQ. M.
L	1.80	X	1.80	X	1	=	3.24	SQ. M.
TOTAL						=	99.72	SQ. M.
NET B/UP OF 1 FLOOR						=	151.38	SQ. M.

PROJECT:-

PROPOSED COMMERCIAL + RESIDENTIAL BUILDING C.T.S. NO. 201, SHUKRAWAR PETH, PUNE.

OWNER — SIGN

1) MR. RAJENDRA BARVE
2) MR. JAYANT BARVE
3) MR. RAVINDRA BARVE
4) MRS. JAYASHREE BARVE

ARCHITECT:-

Rajendra Khire CA/90/13574 — Milind Bhide CA/92/14605

SIGN — SIGN

KHIRE-BHIDE & ASSOCIATES
Architects & Designers
'Jay kamal' Apartment, 336,Narayan Peth,
Near Modi Ganpati, Pune - 411030
Tel. 3020 - 24491587
Email : khirebhideassociats@gmail.com www.khirebhide.com

JOB NO.	DRG.NO.	SCALE	DRAWN BY/CHECK BY
		1:100	MANIK MR. KHIRE
INWARD NO.		—	DATE 04/08/2021
KEY NO.		—	SHEET NO.

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT